

JACKING  
LEVELING  
MOVING

# JEWETT BUILDERS

SILL &  
FOUNDATION  
REPLACEMENT

www.jewettbuilders.com

jewettbuilders@gmail.com

6 Amity Lane • Pittston, ME 04345

(207) 582-1266

FAX (207) 582-5035

JANE BRADLEY

04.26.21

Description of work located at 61 BAYVIEW LANE, BOWDIONHAM  
Future use of building, upon completion of this proposal, is to be: CAMP

## JACK & ROLL CAMP:

Jack and roll building 16'X 28' back 10'-30'  
Building insured for 448 sq ft; coverage = \$ 33,600.00  
Jack up 8' and let down 5' or 6'  
Remove one chimney and truck off  
Install silt fence (for work on camp and garage)

\$ 19,617.00

## SILL WORK:

Replace 88' of pressure treated sill  
Remove and replace 264 sq ft of rough boarding  
Remove and replace 264 sq ft of siding \*(\$6,072.00)  
Replace 28' of pressure treated sleeper  
Sister 336' of 2"x 8" pressure treated floor joist  
Install 84 hangers  
Install 2 lally columns  
\*If owner decides to replace siding deduct stated amount

\$ 25,339.00

## EXCAVATION:

Dig out for foundation 16'x 28'x 6'  
Place waste dirt in old foundation  
Rough backfill foundation frost walls with bank run sand  
Loam & seed 72'x 25'x 4" area  
Remove and truck off 2 stumps

\$ 18,163.00

## DRAINAGE SYSTEM:

Install 88' of inside perimeter footing drainage  
Install 88' of outside perimeter footing drainage  
Tie inside and outside drainage together and run drainage off

\$ 2,424.00

## FOUNDATION:

Pour new base in foundation for chimney (location determined by owner)  
Pour footing 88'x 16"x 8"  
Pour wall 88'x 8'x 8"  
Damp proof 528 sq ft of wall  
Place 448 sq ft of styrofoam under the floor  
Place 3/4" under the floor  
Pour floor 16'x 28'x 4"  
Place 6gauge wire in the floor  
Place 780' of # 4 rebar in the wall and footing  
Place styrofoam down wall 6' and out from wall 2' for 88'

\$ 24,796.00

\$ 90,339.00

JACKING  
LEVELING  
MOVING

# JEWETT BUILDERS

SILL &  
FOUNDATION  
REPLACEMENT

www.jewettbuilders.com

jewettbuilders@gmail.com

6 Amity Lane • Pittston, ME 04345

(207) 582-1266

FAX (207) 582-5035

JANE BRADLEY

04.26.21

Description of work located at 61 BAYVIEW LANE, BOWDIONHAM  
Future use of building, upon completion of this proposal, is to be: GARAGE

## SLAB BID

### JACK & HOLD GARAGE:

Jack and hold building 15'x 21'

Building insured for 315 sq ft; coverage = \$ 23,625.00

\$ 10,514.00

### SLAB WORK:

Excavate top soil and truck off

Pour haunch slab 5'x 21'x 6"

Place 510' of # 4 rebar in the slab & footer

Place ¾" stone under slab

Place 667 sq ft of styrofoam under the slab

Rough backfill exposed styrofoam with ¾" stone

Replace 72' of pressure treated sill

Remove and replace 222 sq ft of rough boarding

Remove and replace 222 sq ft of siding

\$ 31,591.00

\$ 42,105.00

It is the home owner's responsibility to seek all permitting for job proposed,

this includes but is not limited to local, state & DEP

PRICES ARE HONORED FOR 30 DAYS

SEE NEXT PAGE FOR OTHER CONDITIONS REGARDING THIS BID